



GENERAL NOTES:

1. INITIAL BACKFILL MATERIAL SHALL BE THOROUGHLY COMPACTED AROUND PIPE BY SHOVEL SLICING OR TAMPING.
2. SEE SECTION 19 "TRENCH EXCAVATION, BEDDING AND BACKFILL."
3. MINIMUM DEPTH OF BEDDING MATERIAL SHALL BE 1-1/2 INCHES BELOW THE PIPE BELL.
4. FOR ROCKY OR FOR UNSTABLE BEDDING CONDITIONS, SECTION 19-1.07 OF THE STANDARD CONSTRUCTION SPECIFICATIONS SHALL APPLY.
5. IF MINIMUM WIDTH CANNOT BE ACHIEVED, CONTROL DENSITY FILL PER SECTION 50-15 SHALL BE USED IN LIEU OF 3/4" CRUSHED AGGREGATE AT NO EXTRA COST.

DATE: 09/22/2017		NOT TO SCALE	
REVISION	BY	APPROVED	DATE

CITY OF ELK GROVE - PUBLIC WORKS

**STORM DRAIN PIPE BEDDING AND
INITIAL BACKFILL**

APPROVED BY:
Robert M. Muddoch
CITY ENGINEER

10/24/2018
DATE

DRAWING NUMBER
SD - 6.1

